Leakage-controlled evaluation of stacking and recursive feature elimination for diabetes outcome prediction on the PIMA dataset

Subrahmanyam Tanala [a,*]

[a] *Department of Electrical and Electronics Engineering, Anil Neerukonda Institute of Technology and Sciences (ANITS), Visakhapatnam, Andhra Pradesh, India*

Abstract

Background: Machine-learning models for type 2 diabetes risk prediction often report optimistic performance because preprocessing or feature selection is fitted before validation.

Methods: A leakage-controlled pipeline combined median imputation, derived features, recursive feature elimination with cross-validation (RFECV) and an eight-learner stacking ensemble, with every step re-fitted inside each validation split. On the PIMA Indians Diabetes dataset (768 women, 268 with diabetes), 11 learners with prespecified hyperparameters were compared with and without RFECV using 5×10-fold repeated cross-validation with corrected confidence intervals and Holm-adjusted tests, plus a 154-patient hold-out set with DeLong tests. Calibration, thresholds, decision curves and SHAP attributions were also assessed. The framework was replicated in 1815 NHANES 2013–2014 adults with an HbA1c-defined outcome.

Results: RFECV cut inputs by 25% without loss of discrimination. Cross-validated ROC-AUC was 0.843 (95% CI 0.809–0.878) for stacking + RFECV and 0.842 (0.809–0.875) for logistic regression (adjusted $p = 1.00$). On the hold-out set, stacking + RFECV reached sensitivity 0.815, specificity 0.740 and ROC-AUC 0.822; no ROC-AUC difference was significant. Predicted probabilities were systematically too high (calibration intercept −0.62, slope 1.00), consistent with balanced class weighting. In NHANES, logistic regression again matched stacking (0.787 versus 0.785) and the calibration offset recurred (−0.82).

Conclusions: Under leakage-free validation, ensemble complexity gave no discrimination gain over logistic regression in two cohorts, whereas calibration and threshold choice mattered more. These internal results do not es-

*Corresponding author. ORCID: 0009-0003-7760-0522

Email address: subrahmanyam.eee@anits.edu.in (Subrahmanyam Tanala)

tablish clinical transportability.

Keywords: Type 2 diabetes mellitus, Stacked generalisation, Recursive feature elimination, Data leakage, Calibration, Decision curve analysis, PIMA Indians Diabetes

1. Introduction

An estimated 536.6 million adults aged 20–79 years were living with diabetes in 2021, and this number is projected to reach 783.2 million by 2045 [1]. Type 2 diabetes mellitus (T2DM) accounts for the large majority of cases, and a substantial share of people with diabetes are undiagnosed [2]. Because hyperglycaemia damages the kidneys, retina, nerves and vasculature years before symptoms appear, risk estimates from routinely collected measurements could help prioritise confirmatory testing and follow-up.

Machine-learning (ML) classifiers trained on variables such as plasma glucose, body-mass index (BMI), blood pressure and familial risk are a common route to such risk-prediction tools. Two design decisions dominate this literature. The first is feature selection: wrapper methods such as recursive feature elimination (RFE) [3, 4] prune redundant inputs, and RFE with cross-validation (RFECV) chooses the subset size by validated performance. The second is model choice: stacked generalisation [5] trains a meta-learner on the out-of-fold predictions of diverse base learners and is often reported to outperform any single learner.

On small clinical datasets, however, the reported gains of such pipelines are hard to interpret. Imputation, scaling, oversampling or feature selection are frequently fitted on the complete dataset before cross-validation or splitting. This leaks information from the evaluation data into model development and inflates performance [6–8]. Moreover, differences between models are usually reported without confidence intervals or paired tests, calibration is rarely assessed [9], and the default 0.5 decision threshold is seldom justified for the intended use. Systematic comparisons have also found no average performance benefit of flexible ML over logistic regression for clinical prediction [10].

This study therefore asks a deliberately narrow question: *when every data-dependent step is kept inside the validation loop, does combining RFECV with a heterogeneous stacking ensemble improve prediction of the PIMA diabetes outcome over simpler models, and how do calibration and the choice of*

operating threshold affect its interpretation? The contribution is a rigorous evaluation framework, not a new learning algorithm:

1. A leakage-controlled pipeline in which median imputation of physiologically impossible zeros, clinically motivated feature engineering, standardisation, RFECV and an eight-learner stacking ensemble are all re-fitted within the training part of every split.
2. A common feature-selection protocol in which RFECV is fitted once per outer fold and its subset is shared by every compared learner, together with a learner-specific RFECV sensitivity analysis for logistic regression.
3. A statistically explicit evaluation: 5×10-fold repeated cross-validation with corrected confidence intervals and corrected resampled t-tests [11, 12], Holm adjustment for multiplicity [13], bootstrap confidence intervals and DeLong tests [14, 15] on an untouched hold-out set.
4. A clinically oriented assessment that goes beyond discrimination: calibration, pre-specified sensitivity-targeted thresholds, decision-curve analysis [16], a missing-data sensitivity analysis and SHAP explanations [17].
5. A replication of the whole framework in an independent, population-based cohort (NHANES 2013–2014) with a contemporary HbA1c-based outcome [18].

We report where the framework helps and where it does not. In particular, under strict validation and prespecified hyperparameters, the stacking ensemble does not discriminate better than regularised logistic regression on this cohort. Because PIMA predictors include 2-h oral glucose tolerance test (OGTT) values, the setting is risk stratification among people who have already had an OGTT, not population-level screening, and the analysis is primarily a methodological benchmark.

2. Related work

Machine learning on the PIMA cohort. The PIMA Indians Diabetes dataset originates from a long-running longitudinal study of the Gila River Indian Community [19] and was introduced as an ML benchmark with the ADAP neural network [20]. It has since been used to evaluate logistic regression, support vector machines, tree ensembles such as random forests [21], XGBoost [22] and LightGBM [23], and deep networks. Reported accuracies

range from about 0.75 to above 0.98. Recent examples include a Boruta and stacking model reporting 98% accuracy [24] and an RFE–GRU network reporting 90.7% accuracy [25]. By contrast, Reza et al. reported 75.0% (train–test split) and 77.1% (cross-validation) for a stacked model on PIMA [26]. Differences in validation design are one plausible explanation for such a wide spread on a fixed 768-patient dataset, although the cited studies were not independently reproduced or audited here.

Stacking and feature selection for diabetes. Wolpert introduced stacked generalisation [5], and Ting and Witten showed that stacking works best when a simple linear meta-learner receives class probabilities [27]. In *Computers in Biology and Medicine*, Kalagotla et al. combined correlation-based feature selection with a stack of a multilayer perceptron, SVM and logistic regression on PIMA [28]. Idris et al. combined stacking with RFE and isolation-forest outlier removal and reported 79.1% accuracy on PIMA [29]. The combination of RFE-type selection and stacking is therefore not new. What is less common is (i) validating the *whole* chain, including imputation and selection, without leakage; (ii) quantifying uncertainty and testing differences between models; and (iii) reporting calibration and clinical utility alongside discrimination.

Leakage, selection bias and reporting. Ambroise and McLachlan showed that selecting features on the full dataset before cross-validation gives strongly optimistic error estimates [6]. Varma and Simon showed a similar bias when tuning and evaluation share folds [30]. Kaufman et al. formalised data leakage [7], and Kapoor and Narayanan documented leakage across hundreds of ML-based studies in 17 fields [8]. The TRIPOD+AI statement now asks prediction-model studies to report how missing data were handled, how performance was validated, and how calibration and clinical utility were assessed [31]. Our evaluation design follows these recommendations.

3. Materials and methods

Fig. 1 summarises the framework. This study is reported following the TRIPOD+AI recommendations where applicable [31].

3.1. Data

We used the PIMA Indians Diabetes dataset [20]: 768 women of Pima heritage aged at least 21 years, of whom 268 (34.9%) had diabetes. Each




Figure 1: Proposed pipeline. Imputation, feature engineering, standardisation and RFECV are fitted on the training part of each split only. The features retained by RFECV are passed to eight heterogeneous base learners, whose out-of-fold (OOF) probabilities train a logistic-regression meta-learner.

record contains eight predictors: number of pregnancies, 2-h plasma glucose concentration in an oral glucose tolerance test (OGTT; mg/dL), diastolic blood pressure (mm Hg), triceps skin-fold thickness (mm), 2-h serum insulin (µU/mL), BMI (kg/m^2), diabetes pedigree function and age (years). The data are publicly available and de-identified [32].

Outcome definition and intended setting. According to the dataset documentation, the binary outcome indicates whether the woman showed signs of diabetes according to World Health Organization criteria, i.e. a 2-h post-load plasma glucose of at least 200 mg/dL at a survey examination or diagnosis during routine medical care [20, 32]. This outcome is not a contemporary clinical diagnosis of T2DM based on current HbA1c or fasting-glucose criteria [33]. Moreover, the strongest predictor, 2-h OGTT glucose, is itself a diagnostic measurement closely related to the outcome definition. The models studied here therefore address risk stratification among individuals for whom OGTT measurements are already available, not low-cost population screening. We treat the analysis primarily as a methodological benchmark rather than as the development of a clinically deployable diagnostic model.

3.2. Missing values

Zero is physiologically impossible for glucose, blood pressure, skin-fold thickness, insulin and BMI, so these zeros were recoded as missing (Table 1). In the primary analysis, missing values were replaced by the median of the training data in each split. Because insulin is missing for almost half of

the patients, we also compared three alternatives in a sensitivity analysis (Section 3.9).

Table 1: Physiologically impossible zero values recoded as missing ($n = 768$).

Predictor	Missing (n)	Missing (%)
Insulin	374	48.7
Skin-fold thickness	227	29.6
Diastolic blood pressure	35	4.6
BMI	11	1.4
Glucose	5	0.7

3.3. Feature engineering

Eight derived features encoding known T2DM risk interactions were added after imputation, giving 16 candidate predictors for RFECV: the 8 original variables and 8 deterministic derived features (Table 2). Because the derived features are functions of the original variables, the 16 candidates are not informationally independent. The insulin-resistance term follows the HOMA-IR formula [34], but PIMA records 2-h post-load rather than fasting glucose and insulin. We therefore name it `HOMA_IR_surrogate` and do not interpret it as clinical HOMA-IR. The binary thresholds follow the WHO obesity cut-off [35] and the 2-h OGTT threshold for impaired glucose tolerance [33].

3.4. Recursive feature elimination with cross-validation

All features were standardised with training statistics. RFECV started from the 16 candidate predictors. At each step it fitted a random forest (200 trees, balanced class weights), ranked features by impurity-based importance and removed the least important one. Each subset size was scored by stratified 5-fold cross-validated ROC-AUC within the training data, and the size with the highest mean score was retained (minimum three features).

Common versus learner-specific selection. In the model comparison, RFECV was fitted once within each outer training fold using the random-forest ranking estimator, and the resulting subset was supplied to every candidate learner. This gives all learners an identical, leakage-free feature-selection protocol at the cost of one RFECV fit per fold. The subset is optimised with the

Table 2: Derived features. All continuous inputs are measured after imputation.

Feature	Definition	Rationale
`Glucose_BMI`	Glucose × BMI / 100	Joint glycaemia–adiposity effect
`Glucose_Age`	Glucose × Age / 100	Glycaemic risk rising with age
`HOMA_IR_surrogate`	Glucose × Insulin / 405	Insulin-resistance surrogate (post-load)
`Insulin_Glucose_Ratio`	Insulin / Glucose	Insulin response relative to glucose
`BMI_Age`	BMI × Age / 100	Cumulative adiposity exposure
`Obese`	1 if BMI ≥ 30	WHO obesity threshold
`IGT_2h`	1 if Glucose ≥ 140	Impaired glucose tolerance threshold
`Pedigree_Age`	Pedigree × Age	Familial risk expressed over time

random-forest ranking criterion, not separately for each learner. It is therefore *not* equivalent to cross-validating a learner-specific RFECV pipeline for every classifier. To gauge the effect of this choice, we also evaluated logistic regression with its own RFECV ranked by absolute standardised coefficients ("LR-ranked RFECV"). Throughout the article, "+ RFECV" denotes the common random-forest-ranked RFECV subset.

3.5. Stacking ensemble

The level-0 learners were chosen for diversity of inductive bias (Table 3). The level-1 meta-learner was an L2-regularised logistic regression with balanced class weights. It was trained on the positive-class probabilities produced by each base learner for held-out samples in an internal stratified 5-fold split [5, 27]. The base learners were then refitted on all training data for prediction. Gaussian naive Bayes and a depth-5 decision tree were evaluated as additional reference learners but were not part of the stack. Hyperparameters were fixed a priori at conventional settings for small tabular data (Table 3): library defaults where these are standard (e.g. $C = 1$ for LR and SVM), moderate ensemble sizes (200–300 trees), shallow boosting (depth 3) with a small

learning rate (0.05), and a neighbourhood of $k = 15$. They were not tuned, so that no tuning loop could leak into the evaluation. All comparisons between learners are therefore conditional on these prespecified configurations and do not cover every possible tuned version of each algorithm.

Table 3: Level-0 learners and their fixed settings.

Learner	Family	Settings
Logistic regression (LR)	Linear	L2, $C = 1$, balanced class weights
SVM	Kernel	RBF, $C = 1$, balanced weights, Platt-calibrated [36]
k-nearest neighbours	Instance-based	$k = 15$, distance-weighted
Random forest [21]	Bagged trees	300 trees, min. leaf 2, balanced weights
Extra trees	Randomised trees	300 trees, min. leaf 2, balanced weights
Gradient boosting	Boosted trees	200 trees, depth 3, learning rate 0.05
XGBoost [22]	Boosted trees	300 trees, depth 3, rate 0.05, subsample 0.8
LightGBM [23]	Boosted trees	300 trees, 15 leaves, rate 0.05, balanced weights

3.6. Internal evaluation design

Supplementary Fig. S1 shows where each loop runs. The data were split once into a stratified 80% development set (614 patients, 214 with diabetes) and a 20% hold-out set (154 patients, 54 with diabetes), with random seed 42. The split was fixed in code before any model was fitted. Hold-out results of the same prespecified pipeline were inspected in an earlier draft of this work; no learner, hyperparameter, feature or preprocessing choice was changed afterwards, and the hold-out set was not used for any modelling decision.

Repeated cross-validation. On the development set, 11 learners (the eight base learners, naive Bayes, the decision tree and the stack) were compared with and without the common RFECV subset (22 configurations), together with logistic regression with LR-ranked RFECV (23 configurations in total;

Supplementary Table S5), using stratified 10-fold cross-validation repeated five times (50 folds). Within each fold, imputation, feature engineering, standardisation and RFECV were fitted on the nine training folds only. Because fold estimates from overlapping training sets are correlated, we report the mean of each metric with a 95% confidence interval based on the Nadeau–Bengio corrected variance [11],

$$\widehat{\mathrm{Var}}_{\mathrm{corr}} = \left(\frac{1}{J} + \frac{n_{\mathrm{test}}}{n_{\mathrm{train}}}\right) s^2, \tag{1}$$

where $J = 50$ is the number of fold estimates, s^2 their sample variance, and $n_{\mathrm{test}}/n_{\mathrm{train}} = 1/9$. Each configuration was compared with logistic regression on all features using the corrected resampled t-test on paired fold differences ($J - 1$ degrees of freedom) [11, 12]. p-values were adjusted for the 22 comparisons with the Holm procedure [13]. The comparison set was fixed in the analysis code before the repeated cross-validation was run. We chose this test because it is the standard, simulation-validated correction for the dependence between repeated cross-validation folds and has acceptable type I error and good replicability [11, 12]. A nested or paired bootstrap of the whole pipeline would have required refitting RFECV and the stack thousands of times (about 45 s per fit). The full testing procedure is given in Supplementary Section S2.

Hold-out evaluation. The final pipelines were fitted on the full development set and scored once on the hold-out set. ROC-AUC confidence intervals were computed with DeLong's method, and ROC-AUCs of correlated models were compared with DeLong's test [14, 15], with Holm adjustment over the six comparisons. All other metrics were given 95% percentile bootstrap confidence intervals (2000 resamples of the hold-out patients).

3.7. Performance measures

We report accuracy, balanced accuracy, precision (positive predictive value, PPV), recall (sensitivity), specificity, F1, the Matthews correlation coefficient (MCC) [37], ROC-AUC and average precision. Calibration was assessed with the Brier score, calibration-in-the-large (the intercept a of a logistic model with $\operatorname{logit} \hat{p}$ as offset), the calibration slope b from $\operatorname{logit} P(y = 1) = a' + b \operatorname{logit} \hat{p}$, and calibration curves [9]. A well-calibrated model has $a = 0$ and $b = 1$. Calibration was evaluated both on the pooled out-of-fold predictions of the development set and on the hold-out set. The pooled

set contains 3070 predictions: each of the 614 unique development patients is predicted once in each of the five repeats. No recalibration was applied to the reported models. For reference, the development-set prevalence is $\pi = 214/614 = 0.349$, so an intercept correction for balanced class weighting would be $\text{logit}(\pi) = -0.626$.

3.8. Threshold and decision-curve analysis

Instead of using the default 0.5 threshold, we pre-specified operating thresholds targeting 80%, 85%, 90% and 95% sensitivity. Each threshold was chosen on the development-set out-of-fold predictions, using one probability per patient (the mean over the five repeats). The threshold for a target sensitivity s is the $\lceil s\, n_+ \rceil$-th largest predicted probability among the $n_+ = 214$ development positives. Patients are flagged when their probability is greater than or equal to the threshold, so ties at the threshold are flagged and the development sensitivity is at least the target. The thresholds were then applied unchanged to the hold-out set, where sensitivity, specificity, PPV, NPV and the proportion of patients flagged were estimated with bootstrap confidence intervals. Potential clinical utility was assessed by internal decision-curve analysis [16] on the hold-out set, using the net benefit

$$\text{NB}(p_t) = \frac{\text{TP}(p_t)}{n} - \frac{\text{FP}(p_t)}{n} \cdot \frac{p_t}{1 - p_t}, \tag{2}$$

over threshold probabilities p_t from 0.05 to 0.60, and compared with treating all or no patients.

3.9. Missing-data sensitivity analysis

We repeated the development-set comparison of logistic regression and stacking + RFECV (10-fold cross-validation repeated twice) with four imputation strategies, each fitted within the training folds: (i) median imputation; (ii) median imputation plus a binary missingness indicator for every predictor with missing values, which lets the model use informative missingness [38]; (iii) iterative chained-equation imputation (scikit-learn `IterativeImputer`, Bayesian ridge, 20 iterations) [39]; and (iv) k-nearest-neighbour imputation ($k = 10$) [40]. Differences from median imputation were tested with the corrected resampled t-test.

3.10. Replication in an independent cohort

To test whether the methodological conclusions hold beyond PIMA, we reran the identical pipeline and validation design on an independent, population-based cohort: adults aged at least 21 years in the oral glucose tolerance test subsample of the US National Health and Nutrition Examination Survey (NHANES) 2013–2014 [18]. We used the six inputs available in both settings or as close equivalents: sex, age, BMI, diastolic blood pressure, 2-h OGTT glucose and fasting insulin. These yield 13 candidate predictors after feature engineering, because derived features are added only when their inputs exist. NHANES has no pregnancy count, skin-fold thickness or diabetes pedigree function. Insulin is fasting rather than 2-h post-load. NHANES excludes people with diagnosed, treated diabetes from the OGTT, so HbA1c-defined diabetes was too rare to model (58 events). The outcome was therefore dysglycaemia, defined as HbA1c $\geq 5.7\%$ (the ADA threshold for prediabetes or diabetes) [33]. HbA1c is a separate laboratory measurement, so unlike the PIMA outcome it is not defined by the glucose predictor.

The cohort was built from the official CDC public-use files of the 2013–2014 cycle (demographics, body measures, blood pressure, OGTT glucose, insulin and HbA1c; Supplementary Section S9). Diastolic blood pressure was the mean of the valid readings. Of 2345 OGTT participants with a 2-h glucose value, 1858 were aged at least 21 years and 1815 also had fasting insulin and HbA1c. The cohort therefore comprised 1815 adults (929 women) with 551 events (30.4%). BMI was missing for 9 and blood pressure for 41 participants; both were imputed inside the validation folds. This analysis is a *replication* of the evaluation framework on a second cohort, not an external validation of the PIMA-trained model: the predictor definitions and the outcome differ, so the PIMA model cannot be applied to NHANES directly.

3.11. Explainability

We computed Shapley values [17] for the hold-out predictions of the final stacking + RFECV pipeline. The pipeline was treated as one function of the eight raw clinical inputs. Because there are only eight inputs, the values were obtained by exact enumeration of all $2^8 = 256$ feature coalitions (SHAP `ExactExplainer`), with features outside a coalition replaced by values from 40 development-set patients drawn by simple random sampling with seed 42 (an interventional background). They are therefore exact with respect to this background distribution. SHAP values describe how much each input contributed to the model's predictions; they are attributions, not estimates

of causal effects. Explanations are therefore expressed in clinically measured variables, not in engineered or standardised features.

3.12. Implementation and reproducibility

The framework was implemented in Python 3.11 with scikit-learn 1.9 [41], XGBoost 3.2, LightGBM 4.7 and SHAP. Every stochastic step used seed 42: the hold-out split, the repeated outer folds, the inner RFECV and stacking folds, all learners and the RFECV ranker, the iterative imputer, the bootstrap resampling and the SHAP background sample (Supplementary Section S8). Code, configuration, the fold-level results and the scripts that generate every table and figure are publicly available (see Data availability). Every number reported here was produced from repository commit `e23102d`.

4. Results

4.1. Repeated cross-validation

Table 4 and Fig. 2 summarise the 5×10-fold comparison on the development set; Supplementary Table S1 lists all nine metrics with confidence intervals for all 23 configurations. All learners except LightGBM and the single decision tree reached a mean ROC-AUC between 0.820 and 0.846, with overlapping corrected 95% confidence intervals. Stacking on all 16 features had the highest mean ROC-AUC (0.846, 95% CI 0.812–0.880), followed by stacking with the common RFECV subset (0.843, 0.809–0.878) and logistic regression on all features (0.842, 0.809–0.875). The differences between the stacks and logistic regression were small and not statistically significant (+0.004 and +0.001; Holm-adjusted $p = 1.000$ for both). After Holm adjustment, only LightGBM (0.803 and 0.800 without and with RFECV; adjusted $p = 0.044$ and 0.020) and the decision tree (0.770 and 0.772; $p = 0.025$ and 0.020) discriminated significantly worse than logistic regression. No configuration differed significantly from logistic regression in MCC.

At the default 0.5 threshold, the stacks had the highest mean sensitivity among the strong learners (0.763 without and 0.753 with RFECV, compared with 0.744 for logistic regression and 0.655 for the SVM), at the cost of lower specificity (0.757 compared with 0.775 and 0.840). The Platt-calibrated SVM had the lowest mean Brier score (0.156; stacking + RFECV 0.165).

The common RFECV subset changed mean ROC-AUC by at most 0.003 for every learner while reducing the inputs from 16 to a mean of 12.0 features (25% fewer). Logistic regression with its own coefficient-ranked RFECV kept

10.1 features on average and reached a ROC-AUC of 0.840 (0.808–0.873). It performed no better than logistic regression with the common, random-forest-ranked subset (0.842) or with all features.




Figure 2: Cross-validated ROC-AUC of each learner with all 16 features (open circles) and with the common RFECV subset (filled circles). Bars are Nadeau–Bengio corrected 95% confidence intervals over 50 folds. The dashed line marks logistic regression on all features. The stacking ensemble is highlighted.

Table 4: Development-set performance from 5×10-fold repeated cross-validation (50 folds; $n = 614$). Values are means; Nadeau–Bengio corrected 95% confidence intervals are shown in grey beneath. ΔAUC is the mean paired difference from logistic regression on all features, with Holm-adjusted corrected resampled t-test p-values in brackets. "+ RFECV" denotes the common, random-forest-ranked RFECV subset. Sensitivity and specificity use a 0.5 threshold.

Model	Features	ROC-AUC	MCC	Sens.	Spec.	Brier	ΔAUC (adj. p)
Stacking	16.0	0.846 (0.812–0.880)	0.505 (0.431–0.580)	0.763	0.757	0.164	+0.004 (1.000)
Stacking + RFECV	12.0	0.843 (0.809–0.878)	0.497 (0.418–0.575)	0.753	0.757	0.165	+0.001 (1.000)
Logistic regression	16.0	0.842 (0.809–0.875)	0.507 (0.438–0.576)	0.744	0.775	0.163	reference
Logistic regression + RFECV	12.0	0.842 (0.811–0.873)	0.492 (0.418–0.566)	0.717	0.782	0.163	0.000 (1.000)
LR (LR-ranked RFECV)	10.1	0.840 (0.808–0.873)	0.496 (0.426–0.567)	0.731	0.776	0.164	-0.002 (1.000)
SVM	16.0	0.840 (0.802–0.878)	0.505 (0.418–0.591)	0.655	0.840	0.156	-0.002 (1.000)
SVM + RFECV	12.0	0.837 (0.800–0.873)	0.483 (0.393–0.572)	0.643	0.830	0.158	-0.006 (1.000)
Extra trees + RFECV	12.0	0.835 (0.798–0.872)	0.474 (0.393–0.556)	0.693	0.786	0.161	-0.007 (1.000)
Extra trees	16.0	0.835 (0.795–0.874)	0.469 (0.377–0.560)	0.676	0.794	0.160	-0.008 (1.000)
Naive Bayes + RFECV	12.0	0.832 (0.797–0.867)	0.473 (0.393–0.554)	0.624	0.836	0.205	-0.010 (1.000)
Random forest	16.0	0.831 (0.795–0.868)	0.484 (0.390–0.578)	0.712	0.780	0.164	-0.011 (1.000)
Random forest + RFECV	12.0	0.831 (0.797–0.866)	0.492 (0.403–0.581)	0.718	0.781	0.164	-0.011 (1.000)
Gradient boosting	16.0	0.831 (0.798–0.863)	0.436 (0.353–0.518)	0.595	0.828	0.164	-0.011 (1.000)
Naive Bayes	16.0	0.830 (0.793–0.867)	0.494 (0.420–0.568)	0.626	0.852	0.205	-0.012 (1.000)
Gradient boosting + RFECV	12.0	0.830 (0.798–0.862)	0.441 (0.354–0.528)	0.601	0.827	0.164	-0.012 (1.000)
KNN	16.0	0.824 (0.781–0.866)	0.466 (0.375–0.558)	0.611	0.841	0.162	-0.019 (1.000)
XGBoost	16.0	0.821 (0.784–0.857)	0.436 (0.346–0.527)	0.611	0.816	0.173	-0.021 (0.954)
KNN + RFECV	12.0	0.821 (0.777–0.865)	0.458 (0.361–0.554)	0.604	0.839	0.163	-0.022 (1.000)
XGBoost + RFECV	12.0	0.820 (0.785–0.854)	0.440 (0.357–0.524)	0.615	0.817	0.172	-0.023 (0.586)
LightGBM	16.0	0.803 (0.764–0.842)	0.414 (0.321–0.508)	0.622	0.789	0.205	-0.039 (0.044)
LightGBM + RFECV	12.0	0.800 (0.765–0.836)	0.420 (0.336–0.505)	0.627	0.790	0.202	-0.042 (0.020)
Decision tree + RFECV	12.0	0.772 (0.731–0.813)	0.429 (0.348–0.510)	0.767	0.679	0.207	-0.070 (0.020)
Decision tree	16.0	0.770 (0.729–0.811)	0.431 (0.352–0.511)	0.774	0.675	0.210	-0.072 (0.025)

4.2. Selected features and their stability

Across the 50 outer folds, random-forest-ranked RFECV kept a median of 14 features (interquartile range 8–15; range 7–16). Seven features were kept in every fold: glucose, BMI and the engineered `Glucose_BMI`, `Glucose_Age`, `BMI_Age`, `HOMA_IR_surrogate` and `Pedigree_Age` (Fig. 3). The diabetes pedigree function was kept in 94% of folds. The thresholded flags were the weakest candidates: `Obese` was kept in 6% of folds and `IGT_2h` in 38%. They largely duplicate information already carried by BMI and glucose.

Coefficient-ranked RFECV for logistic regression preferred a different, smaller subset (median 10.5 features; range 3–14). It kept glucose in every fold, and age, pregnancies and the pedigree function in more than 90% of folds. It rarely kept blood pressure (2%) and never kept skin-fold thickness. A core of glycaemic, adiposity and diabetes-pedigree predictors was therefore retained by both selectors, but the exact subset depended on the ranking criterion.




Figure 3: Proportion of the 50 outer cross-validation folds in which each candidate feature was retained by random-forest-ranked RFECV (the common protocol) and by coefficient-ranked RFECV for logistic regression. Engineered features are shown in italics.

4.3. Internal hold-out performance

On the 154 hold-out patients (Table 5, Fig. 4), the stacking + RFECV pipeline reached a ROC-AUC of 0.822 (95% CI 0.756–0.888), sensitivity 0.815 (0.709–0.915), specificity 0.740 (0.649–0.823), MCC 0.532 (0.403–0.658) and F1 0.710. It correctly identified 44 of 54 patients with diabetes. Among the evaluated configurations it had the highest observed sensitivity, F1 and MCC on this split. However, the confidence intervals of all models overlapped widely. No ROC-AUC difference between the stacking + RFECV pipeline and any comparator was statistically significant (DeLong test; differences from -0.004 to $+0.013$; smallest Holm-adjusted $p = 0.89$). Supplementary Table S2 gives all hold-out metrics. Random forest + RFECV (0.826) and XGBoost + RFECV (0.824) had slightly higher hold-out ROC-AUC, and average precision ranged from 0.683 (logistic regression) to 0.711 (random forest + RFECV).

Table 5: Hold-out performance ($n = 154$, 54 with diabetes) at a 0.5 threshold. 95% confidence intervals are shown in grey beneath: DeLong for ROC-AUC, percentile bootstrap (2000 resamples) otherwise. AP, average precision. The last column gives the ROC-AUC difference of stacking + RFECV minus the comparator, with Holm-adjusted DeLong p-values.

Model	ROC-AUC	Sensitivity	Specificity	MCC	F1	AP	ΔAUC (adj. p)
Stacking + RFECV	0.822 (0.756–0.888)	0.815 (0.709–0.915)	0.740 (0.649–0.823)	0.532 (0.403–0.658)	0.710 (0.615–0.797)	0.696	–
Stacking	0.819 (0.752–0.885)	0.796 (0.688–0.904)	0.720 (0.631–0.804)	0.494 (0.362–0.625)	0.688 (0.592–0.778)	0.702	+0.003 (1.000)
Logistic regression	0.811 (0.744–0.878)	0.741 (0.625–0.862)	0.740 (0.649–0.825)	0.464 (0.325–0.606)	0.667 (0.564–0.763)	0.683	+0.011 (1.000)
LR + LR-ranked RFECV	0.809 (0.741–0.876)	0.722 (0.608–0.846)	0.740 (0.649–0.825)	0.447 (0.309–0.591)	0.655 (0.551–0.753)	0.684	+0.013 (0.892)
Random forest + RFECV	0.826 (0.761–0.892)	0.685 (0.564–0.804)	0.760 (0.673–0.840)	0.434 (0.290–0.573)	0.643 (0.537–0.739)	0.711	-0.004 (1.000)
XGBoost + RFECV	0.824 (0.758–0.891)	0.648 (0.523–0.776)	0.820 (0.743–0.888)	0.470 (0.321–0.605)	0.654 (0.543–0.752)	0.697	-0.003 (1.000)
SVM	0.810 (0.740–0.880)	0.537 (0.407–0.672)	0.830 (0.755–0.896)	0.383 (0.226–0.534)	0.580 (0.457–0.692)	0.684	+0.012 (1.000)




Figure 4: Hold-out ROC (a) and precision–recall (b) curves for stacking + RFECV, logistic regression and random forest + RFECV. The dotted lines show chance performance and the outcome prevalence (0.35).

4.4. Calibration

All class-weighted models overestimated risk (Table 6, Fig. 5). On the pooled development-set out-of-fold predictions, the calibration intercept was −0.616 for stacking + RFECV and −0.623 for logistic regression. This is almost exactly the logit of the outcome prevalence, $\text{logit}(0.349) = -0.62$, which is consistent with the expected effect of balanced class weighting: weighting the classes equally corresponds to training at a prevalence of 50%, which shifts the model intercept by about $-\text{logit}(\pi)$ for prevalence π. We did not run a controlled experiment without class weights, so this explanation is supported by the arithmetic and by the well-calibrated unweighted Platt layer of the SVM, but it is not formally isolated. The calibration slope of the stack was close to one (1.002), so its spread of risks was appropriate and only its level was shifted. The Platt-calibrated SVM, whose probabilities are refitted without class weights, was well calibrated (intercept −0.029, slope 0.985) and had the lowest Brier score. On the hold-out set, the stack's intercept (−0.624) was unchanged and its slope fell to 0.866, compared with 0.756 for logistic regression.

Table 6: Calibration. Development values use pooled out-of-fold predictions (614×5); hold-out Brier scores have bootstrap 95% CIs. Ideal values: intercept 0, slope 1.

	Development (out-of-fold)			Hold-out		
Model	Brier	Intercept	Slope	Brier (95% CI)	Intercept	Slope
Stacking + RFECV	0.165	-0.616	1.002	0.177 (0.143–0.213)	-0.624	0.866
Logistic regression	0.163	-0.623	0.899	0.181 (0.147–0.219)	-0.629	0.756
Random forest + RFECV	0.164	-0.406	0.823	0.166 (0.134–0.201)	-0.338	0.776
SVM	0.156	-0.029	0.985	0.169 (0.135–0.205)	+0.004	0.844




Figure 5: Calibration curves (deciles of predicted risk) on (a) pooled development-set out-of-fold predictions and (b) the hold-out set (quintiles). Points below the diagonal indicate overestimated risk.

4.5. Operating thresholds and decision-curve analysis

Thresholds fixed on development-set out-of-fold predictions transferred reasonably to the hold-out set (Table 7). For stacking + RFECV, the 80%, 85% and 90% sensitivity targets gave hold-out sensitivities of 0.815, 0.852 and 0.907 and specificities of 0.66, 0.63 and 0.56, flagging 51%–60% of patients for confirmatory testing. The 95% target gave a hold-out sensitivity of 0.926 (0.848–0.983), below target. With only 54 positive patients, each missed case changes sensitivity by 1.9 percentage points. Logistic regression gave very similar operating points; at the 95% target it reached 0.963 with specificity 0.53. NPV was 0.87–0.96 across all thresholds and both models.

In this internal decision-curve analysis (Fig. 6), all three models had higher net benefit than treating all or no patients across threshold probabilities from 0.10 to 0.55; logistic regression fell to zero net benefit at 0.60. The three curves were nearly identical up to a threshold of 0.45 (differences in net benefit of at most 0.03). Above 0.50, the stack retained slightly more net benefit than logistic regression, but this region is based on few patients.

Table 7: Sensitivity-targeted operating points. Thresholds were chosen on development-set out-of-fold predictions and applied unchanged to the hold-out set. Bootstrap 95% CIs are shown in grey beneath. "Flagged" is the proportion of hold-out patients referred for confirmatory testing.

Model	Target	Threshold	Sensitivity	Specificity	PPV	NPV	Flagged
Stacking + RFECV	80%	0.433	0.815 (0.709–0.915)	0.660 (0.559–0.747)	0.564 (0.453–0.670)	0.868 (0.790–0.940)	50.6%
Stacking + RFECV	85%	0.348	0.852 (0.754–0.942)	0.630 (0.529–0.723)	0.554 (0.442–0.658)	0.887 (0.809–0.957)	53.9%
Stacking + RFECV	90%	0.276	0.907 (0.821–0.981)	0.560 (0.459–0.653)	0.527 (0.420–0.622)	0.918 (0.839–0.983)	60.4%
Stacking + RFECV	95%	0.212	0.926 (0.848–0.983)	0.520 (0.423–0.621)	0.510 (0.408–0.606)	0.929 (0.855–0.984)	63.6%
Logistic regression	80%	0.413	0.852 (0.754–0.942)	0.650 (0.551–0.738)	0.568 (0.458–0.671)	0.890 (0.814–0.958)	52.6%
Logistic regression	85%	0.345	0.852 (0.754–0.942)	0.620 (0.520–0.710)	0.548 (0.438–0.654)	0.886 (0.806–0.956)	54.5%
Logistic regression	90%	0.284	0.889 (0.804–0.968)	0.580 (0.480–0.674)	0.533 (0.427–0.633)	0.906 (0.829–0.970)	58.4%
Logistic regression	95%	0.212	0.963 (0.903–1.000)	0.530 (0.431–0.630)	0.525 (0.419–0.624)	0.964 (0.903–1.000)	64.3%




Figure 6: Decision curves on the hold-out set. Net benefit is shown against the threshold probability at which a patient would be referred for confirmatory testing.

4.6. Sensitivity to missing-data handling

The conclusions were robust to the imputation strategy (Table 8). With iterative or k-NN imputation, ROC-AUC changed by at most +0.005 relative to median imputation for both logistic regression and stacking + RFECV (all $p \geq 0.45$). Adding missingness indicators did not help. It lowered the ROC-AUC of logistic regression slightly (-0.010, $p = 0.39$) and left stacking + RFECV unchanged (-0.002, $p = 0.50$), and RFECV retained on average only 1.2 of the five indicators. Under every strategy, stacking and logistic regression remained within 0.005 of each other.

Table 8: Missing-data sensitivity analysis on the development set (10-fold cross-validation repeated twice; 20 folds). ROC-AUC values are means with corrected 95% CIs. ΔAUC is the paired difference from median imputation for the same model, with the corrected resampled t-test p-value.

Model	Imputation	Features	ROC-AUC (95% CI)	MCC	Sens.	Brier	ΔAUC (p)
Logistic regression	Median	16.0	0.846 (0.813–0.878)	0.514	0.743	0.162	reference
Logistic regression	Median + indicators	21.0	0.836 (0.788–0.884)	0.484	0.727	0.166	-0.010 (0.387)
Logistic regression	Iterative (MICE-style)	16.0	0.847 (0.814–0.879)	0.517	0.753	0.162	+0.001 (0.712)
Logistic regression	KNN ($k = 10$)	16.0	0.847 (0.813–0.880)	0.505	0.743	0.162	+0.001 (0.607)
Stacking + RFECV	Median	11.3	0.844 (0.804–0.883)	0.498	0.752	0.164	reference
Stacking + RFECV	Median + indicators	13.3	0.841 (0.799–0.884)	0.496	0.748	0.166	-0.002 (0.503)
Stacking + RFECV	Iterative (MICE-style)	14.0	0.848 (0.815–0.880)	0.512	0.762	0.163	+0.004 (0.594)
Stacking + RFECV	KNN ($k = 10$)	13.6	0.849 (0.814–0.884)	0.501	0.759	0.163	+0.005 (0.448)

4.7. Replication in NHANES 2013–2014

The main findings replicated in the independent NHANES cohort (Table 9). Overall discrimination was lower than in PIMA, as expected for an outcome not defined by the glucose predictor. In 5×10-fold cross-validation, stacking and logistic regression were practically equivalent: logistic regression reached 0.787 (95% CI 0.763–0.811) on all 13 candidates and 0.789 (0.764–0.814) with its own coefficient-ranked RFECV, compared with 0.785 (0.758–0.812) for stacking + RFECV. The difference between stacking + RFECV and logistic regression was −0.001 (Holm-adjusted $p = 1.00$). Most single flexible learners discriminated less well than logistic regression in this larger cohort. After Holm adjustment, random forest, XGBoost, the SVM, k-NN, LightGBM and the decision tree were significantly worse with and without RFECV (for example random forest + RFECV 0.755, XGBoost + RFECV 0.757, SVM 0.755, LightGBM + RFECV 0.735; all adjusted $p \leq 0.037$), whereas gradient boosting, naive Bayes and extra trees + RFECV were not. RFECV reduced the candidates from 13 to a mean of 9.4 without loss of discrimination. It kept the engineered `Glucose_BMI`, `Glucose_Age` and `BMI_Age` in every fold, and 2-h glucose and `HOMA_IR_surrogate` in 88%.

On the 363-patient NHANES hold-out set (110 events), stacking + RFECV reached a ROC-AUC of 0.783 (0.736–0.831), sensitivity 0.709, specificity 0.704 and MCC 0.384. Logistic regression reached 0.777 (0.729–0.825), and no DeLong comparison was significant (smallest adjusted $p = 0.72$). The hold-out estimates agreed closely with the cross-validated ones.

The calibration finding replicated closely. On pooled out-of-fold predictions, the calibration intercept was −0.821 for stacking + RFECV and

−0.834 for logistic regression. The logit of the NHANES development-set prevalence is −0.83, so the offset again matched the shift expected from balanced class weighting. The calibration slope of the stack was 1.025. The unweighted, Platt-calibrated SVM was again well calibrated (intercept −0.014, slope 0.987). In SHAP attributions, age, 2-h glucose and BMI dominated (mean |SHAP| 0.152, 0.072 and 0.064). Sex, blood pressure and insulin received zero attribution, because the final RFECV subset (`Glucose_BMI`, `Glucose_Age`, `BMI_Age`) contains no feature derived from them.

Table 9: Replication of the evaluation in NHANES 2013–2014 (1815 adults; outcome HbA1c $\geq 5.7\%$), alongside the PIMA results. Cross-validated ROC-AUC is the 5×10-fold mean with Nadeau–Bengio corrected 95% CI beneath. NHANES ΔAUC is the paired difference from logistic regression on all candidates (Holm-adjusted p). Hold-out ROC-AUC has DeLong 95% CI beneath; the last column is stacking + RFECV minus the comparator (Holm-adjusted DeLong p). The PIMA model was not applied to NHANES, because predictors and outcome differ.

	PIMA	NHANES cross-validation		NHANES hold-out ($n = 363$)	
Model	CV ROC-AUC	ROC-AUC	ΔAUC vs LR (adj. p)	ROC-AUC	ΔAUC (adj. p)
Stacking + RFECV	0.843 (0.809–0.878)	0.785 (0.758–0.812)	-0.001 (1.000)	0.783 (0.736–0.831)	–
Stacking	0.846 (0.812–0.880)	0.786 (0.761–0.811)	-0.001 (1.000)	0.783 (0.736–0.831)	0.000 (1.000)
Logistic regression	0.842 (0.809–0.875)	0.787 (0.763–0.811)	reference	0.777 (0.729–0.825)	+0.006 (1.000)
LR + LR-ranked RFECV	0.840 (0.808–0.873)	0.789 (0.764–0.814)	+0.003 (1.000)	0.783 (0.735–0.830)	0.000 (1.000)
Random forest + RFECV	0.831 (0.797–0.866)	0.755 (0.725–0.784)	-0.032 (0.006)	0.766 (0.717–0.816)	+0.017 (0.719)
XGBoost + RFECV	0.820 (0.785–0.854)	0.757 (0.730–0.784)	-0.029 (0.003)	0.776 (0.728–0.825)	+0.007 (1.000)
SVM	0.840 (0.802–0.878)	0.755 (0.732–0.779)	-0.031 (<0.001)	0.766 (0.714–0.817)	+0.018 (0.743)

4.8. Explanation of predictions

In PIMA, glucose dominated the SHAP explanations of the stacking + RFECV pipeline (mean |SHAP| = 0.170 on the probability scale), followed by BMI (0.074), age (0.055), the diabetes pedigree function (0.038) and pregnancies (0.028) (Fig. 7). Insulin, skin-fold thickness and blood pressure contributed little (at most 0.015). Higher glucose, BMI, age and pedigree values consistently increased the predicted probability. These inputs contributed

most to the model's predictions, in directions that agree with established risk factors; as model attributions, they do not measure causal effects. Because the outcome itself is largely defined by 2-h post-load glucose, the dominance of glucose in particular should not be interpreted as evidence of independent causal importance.




Figure 7: SHAP values of the hold-out predictions of the stacking + RFECV pipeline, expressed in the eight raw clinical inputs. Each point is one patient; colour shows the feature value.

5. Discussion

5.1. Principal findings

Under a validation design in which every data-dependent step was refitted inside each split, combining RFECV with an eight-learner stacking ensemble did not improve discrimination over regularised logistic regression on the PIMA cohort, under the prespecified hyperparameter configurations evaluated here. Across 50 cross-validation folds, the stacks and logistic regression differed by less than 0.005 in ROC-AUC, and no difference approached significance after accounting for correlated folds and multiple comparisons. The same held on the hold-out set, where every DeLong comparison was non-significant. The higher hold-out sensitivity, F1 and MCC of stacking + RFECV (0.815, 0.710 and 0.532) are best read as the highest observed values on one 154-patient split, not as evidence of superiority. Its bootstrap confidence intervals overlap those of every comparator.

This null result is itself the central finding: added ensemble complexity did not produce a measurable benefit once validation was leakage-free. It also

replicated in an independent, population-based NHANES cohort with a different, HbA1c-based outcome. There, logistic regression again matched the stack in cross-validation (0.787 versus 0.785), and most single flexible learners, including the tree ensembles, performed significantly worse. It agrees with the systematic finding that flexible ML methods offer no average discrimination benefit over logistic regression in clinical prediction [10]. It also contrasts with the very high accuracies (0.90–0.98) sometimes reported for complex pipelines on the same 768 patients [24, 25]. We cannot reproduce or audit those studies. In our leakage-controlled analysis, no configuration exceeded a cross-validated ROC-AUC of about 0.85 on eight routine variables with a 35% prevalence. Differences in validation design, especially preprocessing and feature selection outside the resampling loop [6, 8], are one plausible explanation for the higher reported values.

5.2. What RFECV and stacking contribute

RFECV reduced the inputs by about a quarter with no loss of discrimination and identified a stable feature core of glycaemic, adiposity and diabetes-pedigree predictors, consistent with the SHAP attributions; the full selected subset was not stable and varied in size between folds. The engineered interactions (`Glucose_BMI`, `Glucose_Age`, `BMI_Age`, `HOMA_IR_surrogate`, `Pedigree_Age`) were consistently preferred over thresholded flags and over raw blood pressure or skin-fold thickness. Two caveats apply. First, the selected size varied widely between folds (7–16 features) because the RFECV score curve is flat above about six features. A one-standard-error rule or stability selection [42] would yield smaller and more reproducible subsets. Second, the subset depended on the ranking estimator: coefficient-ranked RFECV for logistic regression chose different features than random-forest-ranked RFECV. The common protocol used here ensures a fair, identical selection procedure across learners, but it is not a learner-specific optimum, and results for individual learners should be read with that in mind.

Stacking did not materially change discrimination and performed similarly across the evaluated validation settings: it was never significantly worse than the best single learner, and at the default threshold it operated at somewhat higher sensitivity. Against this stand higher computational cost (one stacking + RFECV fit took about 45 s, compared with milliseconds for logistic regression) and reduced transparency. In this cohort and under the evaluated configurations, logistic regression provided a substantially simpler model without measurable loss of discrimination.

5.3. Calibration and thresholds matter more than the choice of learner

The largest practical difference between configurations was not discrimination but calibration, and this is one of the main findings of the study: high discrimination did not imply well-calibrated probabilities. Predicted probabilities were shifted upwards by almost exactly the logit of the prevalence, consistent with the expected effect of balanced class weights, which are widely used to raise sensitivity on imbalanced data. The calibration slope stayed near one. Class weighting can in general also change fitted parameters and the ranking of patients; with the approximately unchanged slope observed here, its principal effect appears to be a shift in the level of the probabilities rather than a major change in ranking. Either way, the predicted probabilities cannot be read as absolute risks without recalibration [9]. A simple intercept correction or Platt rescaling without class weights, fitted on out-of-fold predictions, would remove this offset. The well-calibrated SVM in our comparison shows the effect directly. The same offset appeared in NHANES (intercept -0.82 against a prevalence logit of -0.83), while the unweighted SVM was again well calibrated. This reproduction in a second cohort with a different outcome makes class weighting the most plausible explanation, although it was still not isolated experimentally. Reporting only discrimination metrics, as most PIMA studies do, would have hidden this issue entirely.

Similarly, the default 0.5 threshold is arbitrary for risk stratification. Thresholds chosen on development data for 80%–90% sensitivity transferred to the hold-out set within sampling error, at a cost of referring roughly half to 60% of patients for confirmatory testing. In this internal decision-analytic assessment, decision curves showed positive net benefit over a plausible range of thresholds, indicating potential utility at selected thresholds. This does not demonstrate clinical usefulness, which would require external validation, prospective evaluation in a real workflow and an analysis of costs. All three models also gave nearly identical net benefit, so the choice of operating threshold was more consequential than the choice between stacking and logistic regression.

5.4. Missing data

Almost half of the insulin values and 30% of the skin-fold values were missing, so missingness itself might be expected to carry predictive information [38]. In this cohort it did not. Missingness indicators slightly reduced discrimination, and iterative or k-NN imputation gave the same results as

the simpler median imputation. The low SHAP contributions of insulin and skin-fold thickness agree with this. Whatever information these partially observed variables carry is largely redundant with glucose and BMI. Median imputation fitted within training folds was therefore adequate for this PIMA analysis under the evaluated alternatives; this may not hold in other cohorts, particularly where tests are ordered selectively.

5.5. Methodological benchmark, not a clinical model

Taken together, these results should be read as a methodological benchmark of internal validity. They show how much of the apparent performance of a complex pipeline survives leakage-free validation, uncertainty quantification and calibration assessment on PIMA. They do not provide a clinically validated diabetes risk model, which would require a contemporary outcome definition, predictors available before diagnostic testing, and external validation.

5.6. Limitations

- **One small, historical, specific cohort.** PIMA comprises 768 women of Pima heritage from a single historical study. The reported performance is internal validation on this cohort and should not be interpreted as evidence of clinical transportability to men, other populations or other care settings. With 268 events and 16 candidate predictors, the cohort is also small for flexible model development [43].

- **Outcome definition.** The PIMA outcome is diabetes according to WHO criteria at the time of the original study, largely defined by 2-h post-load glucose. It is not a contemporary clinical diagnosis of type 2 diabetes based on HbA1c-based criteria, and it is closely related to the strongest predictor. The analysis is therefore a methodological benchmark, not a clinically deployable diagnostic model.

- **Replication, not external validation of a model.** The NHANES analysis re-ran the evaluation framework on a second cohort; it did not apply the PIMA-trained model to new patients, because predictors (no pregnancy count, skin-fold thickness or pedigree function; fasting insulin) and outcome (HbA1c $\geq 5.7\%$) differ. It supports the methodological conclusions, not the transportability of any particular model.

- **One hold-out split.** With 54 positive hold-out patients, confidence intervals are wide. We therefore base inference on the 50-fold repeated cross-validation and treat hold-out results as confirmatory.

- **Fixed hyperparameters.** Learners were not tuned, to avoid an additional selection loop. Our comparisons therefore apply to the prespecified configurations only; nested tuning could improve individual learners such as XGBoost, LightGBM or the SVM, although the cross-validated ceiling suggests limited headroom.

- **Post-load measurements.** PIMA glucose and insulin are 2-h OGTT values, so `HOMA_IR_surrogate` is not a clinical HOMA-IR, and the model applies to settings where an OGTT has already been performed.

5.7. Future work

Future work should (i) validate the pipeline externally on larger, more diverse cohorts; (ii) incorporate recalibration and threshold selection into the nested pipeline; (iii) compare RFECV with stability selection and with learner-specific nested RFECV; and (iv) assess fairness and transportability across sex and ethnicity, as recommended by TRIPOD+AI [31].

6. Conclusion

This study evaluated a leakage-controlled framework combining RFECV with heterogeneous stacking for prediction of the PIMA diabetes outcome. Repeated cross-validation showed that the common random-forest-ranked RFECV reduced the predictor set by about a quarter without materially changing discrimination. Under the prespecified hyperparameters, stacking did not significantly improve ROC-AUC over regularised logistic regression (0.843 versus 0.842). The stacking model provided sensitivity-oriented operating points, with the highest observed hold-out sensitivity (0.815) and MCC (0.532) on this split. However, its class-weighted probabilities were systematically miscalibrated and should not be interpreted as absolute risks without recalibration. These conclusions, including the calibration offset, replicated in an independent NHANES 2013–2014 cohort with an HbA1c-defined outcome. Threshold and decision-curve analyses further indicated that the choice of operating threshold may be more consequential than the

choice between stacking and logistic regression. Because the predictors include 2-h OGTT values and the outcome is a historical WHO-criteria definition, these findings are a methodological benchmark of internal validity on the PIMA cohort, not a clinically validated model, and require external validation before any clinical application.

CRediT authorship contribution statement

Subrahmanyam Tanala: Conceptualization, Methodology, Software, Formal analysis, Investigation, Visualization, Writing – original draft, Writing – review & editing.

Declaration of competing interest

The author declares no known competing financial interests or personal relationships that could have appeared to influence the work reported in this paper.

Funding

This research did not receive any specific grant from funding agencies in the public, commercial, or not-for-profit sectors.

Ethics statement

This study used only publicly available, de-identified data: the PIMA Indians Diabetes dataset and the NHANES 2013–2014 public-use files. NHANES protocols were approved by the NCHS Research Ethics Review Board and participants gave written informed consent. No new data were collected from human participants, so ethical approval and informed consent were not required.

Data and code availability

The PIMA Indians Diabetes dataset is publicly available [32] and is included in the repository as `data/diabetes.csv` (768 records, header row added; source mirror and SHA-256 checksum in Supplementary Section S8). All code, configuration files, fold-level results and the scripts that regenerate every table and figure in this article are available at `https://github.c`

om/subrahmanyamtanala-rgb/T2D. The NHANES 2013–2014 replication cohort [18] is included as data/nhanes_2013_2014_ogtt.csv, together with the six official CDC public-use files it is built from (data/nhanes_cdc/); its construction is described in Supplementary Section S9. All PIMA results were produced from commit e23102d; the NHANES results are in results/external_nhanes/. The full analysis can be reproduced with python -m t2d.analysis -stage cv, -stage holdout and -stage missing, followed by python paper/make_assets.py.

Supplementary material

Supplementary material includes the nested validation diagram (Fig. S1), the full statistical testing procedure, results for all configurations and metrics (Tables S1–S3), a TRIPOD+AI reporting map (Table S4), the list of all 23 configurations (Table S5), reproduction instructions including every random seed, and the construction of the NHANES cohort (Section S9).

Declaration of generative AI and AI-assisted technologies in the manuscript preparation process

During the preparation of this work the author used Claude (Anthropic) to assist with software development, statistical analysis code and drafting of the manuscript text. After using this tool, the author reviewed and edited the content as needed and takes full responsibility for the content of the published article.

References

[1] H. Sun, P. Saeedi, S. Karuranga, et al., IDF Diabetes Atlas: Global, regional and country-level diabetes prevalence estimates for 2021 and projections for 2045, Diabetes Research and Clinical Practice 183 (2022) 109119. doi:10.1016/j.diabres.2021.109119.

[2] International Diabetes Federation, IDF Diabetes Atlas, 10th Edition, International Diabetes Federation, Brussels, Belgium, 2021.

[3] I. Guyon, J. Weston, S. Barnhill, V. Vapnik, Gene selection for cancer classification using support vector machines, Machine Learning 46 (2002) 389–422. doi:10.1023/A:1012487302797.

[4] R. Kohavi, G. H. John, Wrappers for feature subset selection, Artificial Intelligence 97 (1–2) (1997) 273–324. doi:10.1016/S0004-3702(97)00043-X.

[5] D. H. Wolpert, Stacked generalization, Neural Networks 5 (2) (1992) 241–259. doi:10.1016/S0893-6080(05)80023-1.

[6] C. Ambroise, G. J. McLachlan, Selection bias in gene extraction on the basis of microarray gene-expression data, Proceedings of the National Academy of Sciences of the United States of America 99 (10) (2002) 6562–6566. doi:10.1073/pnas.102102699.

[7] S. Kaufman, S. Rosset, C. Perlich, O. Stitelman, Leakage in data mining: Formulation, detection, and avoidance, ACM Transactions on Knowledge Discovery from Data 6 (4) (2012) 15. doi:10.1145/2382577.2382579.

[8] S. Kapoor, A. Narayanan, Leakage and the reproducibility crisis in machine-learning-based science, Patterns 4 (9) (2023) 100804. doi:10.1016/j.patter.2023.100804.

[9] B. Van Calster, D. J. McLernon, M. van Smeden, L. Wynants, E. W. Steyerberg, Calibration: the Achilles heel of predictive analytics, BMC Medicine 17 (2019) 230. doi:10.1186/s12916-019-1466-7.

[10] E. Christodoulou, J. Ma, G. S. Collins, E. W. Steyerberg, J. Y. Verbakel, B. Van Calster, A systematic review shows no performance benefit of machine learning over logistic regression for clinical prediction models, Journal of Clinical Epidemiology 110 (2019) 12–22. doi:10.1016/j.jclinepi.2019.02.004.

[11] C. Nadeau, Y. Bengio, Inference for the generalization error, Machine Learning 52 (3) (2003) 239–281. doi:10.1023/A:1024068626366.

[12] R. R. Bouckaert, E. Frank, Evaluating the replicability of significance tests for comparing learning algorithms, in: Advances in Knowledge Discovery and Data Mining (PAKDD 2004), Vol. 3056 of Lecture Notes in Computer Science, Springer, 2004, pp. 3–12. doi:10.1007/978-3-540-24775-3_3.

[13] S. Holm, A simple sequentially rejective multiple test procedure, Scandinavian Journal of Statistics 6 (2) (1979) 65–70.

[14] E. R. DeLong, D. M. DeLong, D. L. Clarke-Pearson, Comparing the areas under two or more correlated receiver operating characteristic curves: a nonparametric approach, Biometrics 44 (3) (1988) 837–845. doi:10.2307/2531595.

[15] X. Sun, W. Xu, Fast implementation of DeLong's algorithm for comparing the areas under correlated receiver operating characteristic curves, IEEE Signal Processing Letters 21 (11) (2014) 1389–1393. doi:10.1109/LSP.2014.2337313.

[16] A. J. Vickers, E. B. Elkin, Decision curve analysis: a novel method for evaluating prediction models, Medical Decision Making 26 (6) (2006) 565–574. doi:10.1177/0272989X06295361.

[17] S. M. Lundberg, S.-I. Lee, A unified approach to interpreting model predictions, in: Advances in Neural Information Processing Systems 30, 2017, pp. 4765–4774.

[18] Centers for Disease Control and Prevention, National Center for Health Statistics, National health and nutrition examination survey (NHANES) 2013–2014, https://wwwn.cdc.gov/nchs/nhanes/continuousnhanes/default.aspx?BeginYear=2013, public-use data files DEMO_H, BMX_H, BPX_H, OGTT_H, INS_H and GHB_H (2016).

[19] W. C. Knowler, P. H. Bennett, R. F. Hamman, M. Miller, Diabetes incidence and prevalence in Pima Indians: a 19-fold greater incidence than in Rochester, Minnesota, American Journal of Epidemiology 108 (6) (1978) 497–505. doi:10.1093/oxfordjournals.aje.a112648.

[20] J. W. Smith, J. E. Everhart, W. C. Dickson, W. C. Knowler, R. S. Johannes, Using the ADAP learning algorithm to forecast the onset of diabetes mellitus, in: Proceedings of the Annual Symposium on Computer Applications in Medical Care, 1988, pp. 261–265.

[21] L. Breiman, Random forests, Machine Learning 45 (2001) 5–32. doi:10.1023/A:1010933404324.

[22] T. Chen, C. Guestrin, XGBoost: A scalable tree boosting system, in: Proceedings of the 22nd ACM SIGKDD International Conference on Knowledge Discovery and Data Mining, 2016, pp. 785–794. doi:10.1145/2939672.2939785.

[23] G. Ke, Q. Meng, T. Finley, T. Wang, W. Chen, W. Ma, Q. Ye, T.-Y. Liu, LightGBM: A highly efficient gradient boosting decision tree, in: Advances in Neural Information Processing Systems 30, 2017, pp. 3146–3154.

[24] H. Zhou, Y. Xin, S. Li, A diabetes prediction model based on Boruta feature selection and ensemble learning, BMC Bioinformatics 24 (2023) 224. doi:10.1186/s12859-023-05300-5.

[25] M. Y. Shams, Z. Tarek, A. M. Elshewey, A novel RFE-GRU model for diabetes classification using PIMA Indian dataset, Scientific Reports 15 (2025). doi:10.1038/s41598-024-82420-9.

[26] M. S. Reza, R. Amin, R. Yasmin, W. Kulsum, S. Ruhi, Improving diabetes disease patients classification using stacking ensemble method with PIMA and local healthcare data, Heliyon 10 (2) (2024) e24536. doi:10.1016/j.heliyon.2024.e24536.

[27] K. M. Ting, I. H. Witten, Issues in stacked generalization, Journal of Artificial Intelligence Research 10 (1999) 271–289. doi:10.1613/jair.594.

[28] S. K. Kalagotla, S. V. Gangashetty, K. Giridhar, A novel stacking technique for prediction of diabetes, Computers in Biology and Medicine 135 (2021) 104554. doi:10.1016/j.compbiomed.2021.104554.

[29] N. F. Idris, M. A. Ismail, M. I. Mohd Jaya, A. O. Ibrahim, A. W. Abulfaraj, F. Binzagr, Stacking with recursive feature elimination-isolation forest for classification of diabetes mellitus, PLOS ONE 19 (5) (2024) e0302595. doi:10.1371/journal.pone.0302595.

[30] S. Varma, R. Simon, Bias in error estimation when using cross-validation for model selection, BMC Bioinformatics 7 (2006) 91. doi:10.1186/1471-2105-7-91.

[31] G. S. Collins, K. G. M. Moons, P. Dhiman, et al., TRIPOD+AI statement: updated guidance for reporting clinical prediction models that use regression or machine learning methods, BMJ 385 (2024) e078378. doi:10.1136/bmj-2023-078378.

[32] National Institute of Diabetes and Digestive and Kidney Diseases, Pima Indians diabetes database, UCI Machine Learning Repository; mirrored at https://www.kaggle.com/datasets/uciml/pima-indians-diabetes-database, accessed October 2026 (1990).

[33] American Diabetes Association Professional Practice Committee, 2. Diagnosis and classification of diabetes: Standards of Care in Diabetes—2024, Diabetes Care 47 (Suppl. 1) (2024) S20–S42. doi:10.2337/dc24-S002.

[34] D. R. Matthews, J. P. Hosker, A. S. Rudenski, B. A. Naylor, D. F. Treacher, R. C. Turner, Homeostasis model assessment: insulin resistance and β-cell function from fasting plasma glucose and insulin concentrations in man, Diabetologia 28 (7) (1985) 412–419. doi:10.1007/BF00280883.

[35] World Health Organization, Obesity: Preventing and managing the global epidemic. Report of a WHO consultation, WHO Technical Report Series 894, World Health Organization, Geneva (2000).

[36] J. C. Platt, Probabilistic outputs for support vector machines and comparisons to regularized likelihood methods, in: A. J. Smola, P. Bartlett, B. Schölkopf, D. Schuurmans (Eds.), Advances in Large Margin Classifiers, MIT Press, Cambridge, MA, 1999, pp. 61–74.

[37] D. Chicco, G. Jurman, The advantages of the Matthews correlation coefficient (MCC) over F1 score and accuracy in binary classification evaluation, BMC Genomics 21 (2020) 6. doi:10.1186/s12864-019-6413-7.

[38] M. Sperrin, G. P. Martin, R. Sisk, N. Peek, Missing data should be handled differently for prediction than for description or causal explanation, Journal of Clinical Epidemiology 125 (2020) 183–187. doi:10.1016/j.jclinepi.2020.03.028.

[39] S. van Buuren, K. Groothuis-Oudshoorn, mice: Multivariate imputation by chained equations in R, Journal of Statistical Software 45 (3) (2011) 1–67. doi:10.18637/jss.v045.i03.

[40] O. Troyanskaya, M. Cantor, G. Sherlock, P. Brown, T. Hastie, R. Tibshirani, D. Botstein, R. B. Altman, Missing value estimation methods for DNA microarrays, Bioinformatics 17 (6) (2001) 520–525. doi:10.1093/bioinformatics/17.6.520.

[41] F. Pedregosa, G. Varoquaux, A. Gramfort, V. Michel, B. Thirion, O. Grisel, M. Blondel, P. Prettenhofer, R. Weiss, V. Dubourg, J. Vanderplas, A. Passos, D. Cournapeau, M. Brucher, M. Perrot, É. Duchesnay, Scikit-learn: Machine learning in Python, Journal of Machine Learning Research 12 (2011) 2825–2830.

[42] N. Meinshausen, P. Bühlmann, Stability selection, Journal of the Royal Statistical Society: Series B (Statistical Methodology) 72 (4) (2010) 417–473. doi:10.1111/j.1467-9868.2010.00740.x.

[43] R. D. Riley, J. Ensor, K. I. E. Snell, et al., Calculating the sample size required for developing a clinical prediction model, BMJ 368 (2020) m441. doi:10.1136/bmj.m441.